

ITEM	DWG NO.	CSI NO	DESCRIPTION	QTY.	Wastage	Qty w/ Wastage	UNIT	Unit Material Cost	Unit Labor Cost	Total Material Cost	Total Labor Cost	TOTAL COST
152			3-5/8" Metal Framing CFMF @ 16" O.C (1'-0" L)	64	0%	64	EA	\$ 2.14	\$ 4.3	\$137	\$275	\$412
153			6" Metal Framing CFMF @ 16" O.C (4'-6" L)	8	0%	8	EA	\$ 14.21	\$ 13.0	\$118	\$108	\$225
			Exterior Wall As Per Section 2/3.01 As:									
154			(One Layer) 5/8" Type X Gypsum Wall Board On One Side (4'x8' Sheets)	34	0%	34	EA	\$ 17.48	\$ 24.5	\$602	\$842	\$1,444
155			Tapping	551	10%	606	LF	\$ 0.16	\$ 0.1	\$97	\$55	\$151
156			Mudding	57	10%	63	LBS	\$ 3.50	\$ 1.2	\$220	\$76	\$296
157			Screws	1549	0%	1549	EA	\$ 0.02	\$ 0.0	\$31	\$15	\$46
158			(6") Metal Studs @ 16" O.C (14' H)	28	0%	28	EA	\$ 56.42	\$ 32.6	\$1,557	\$901	\$2,458
159			(6") Metal Top And Bottom Plate (10' L)	7	0%	7	EA	\$ 42.20	\$ 32.6	\$310	\$240	\$549
160			(6") Metal Studs @ 16" O.C (16' H)	28	0%	28	EA	\$ 56.42	\$ 32.6	\$1,557	\$901	\$2,458
161			(6") Metal Top And Bottom Plate (10' L)	7	0%	7	EA	\$ 42.20	\$ 32.6	\$310	\$240	\$549
162			R-6 (1-1/2") Wall Sheathing Panel (4'x8' Sheets)	34	0%	34	EA	\$ 26.64	\$ 26.7	\$917	\$920	\$1,837
163			Sealant	73	10%	81	LF	\$ 0.68	\$ 0.5	\$55	\$36	\$91
164			7/8" Furring Channel @ 16" O.C (10'-0" L)	15	0%	15	EA	\$ 9.45	\$ 6.7	\$139	\$99	\$238
165			6" Metal Framing CFMF @ 16" O.C (5'-4" L)	28	0%	28	EA	\$ 14.21	\$ 13.0	\$392	\$359	\$752
			Exterior Wall As Per Section 2/3.04 As:									
166			(One Layer) 5/8" Type X Gypsum Wall Board On One Side (4'x8' Sheets)	41	0%	41	EA	\$ 17.48	\$ 24.5	\$713	\$998	\$1,711
167			Tapping	653	10%	718	LF	\$ 0.16	\$ 0.1	\$115	\$65	\$179
168			Mudding	68	10%	75	LBS	\$ 3.50	\$ 1.2	\$261	\$90	\$351
169			Screws	1835	0%	1835	EA	\$ 0.02	\$ 0.0	\$37	\$18	\$55
170			Sealant	100	10%	110	LF	\$ 0.68	\$ 0.5	\$75	\$50	\$125
171			(6") Metal Studs @ 16" O.C (13' H)	75	0%	75	EA	\$ 56.42	\$ 32.6	\$4,259	\$2,464	\$6,723
172			(6") Metal Top And Bottom Plate (10' L)	20	0%	20	EA	\$ 42.20	\$ 32.6	\$847	\$655	\$1,503
173			(2-1/2") Metal Studs @ 16" O.C (13' H)	75	0%	75	EA	\$ 23.45	\$ 23.2	\$1,770	\$1,748	\$3,518
174			(2-1/2") Metal Top And Bottom Plate (10' L)	20	0%	20	EA	\$ 18.68	\$ 23.2	\$375	\$465	\$840
175			R-6 (1-1/2") Wall Sheathing Panel (4'x8' Sheets)	41	0%	41	EA	\$ 26.64	\$ 26.7	\$1,087	\$1,091	\$2,177
176			7/8" Furring Channel @ 16" O.C (10'-0" L)	13	0%	13	EA	\$ 9.45	\$ 6.7	\$125	\$89	\$214
177			3-5/8" Metal Framing CFMF @ 16" O.C (3'-6" L)	38	0%	38	EA	\$ 5.63	\$ 3.5	\$213	\$130	\$343
			CEILING									
178			(5/8") Type X Gypsum Board Ceiling (4'x8' Sheets)	77	0%	77	EA	\$ 17.48	\$ 24.5	\$1,352	\$1,893	\$3,246
179			Tapping	1238	10%	1362	LF	\$ 0.16	\$ 0.1	\$218	\$123	\$340
180			Mudding	129	10%	142	LBS	\$ 3.50	\$ 1.2	\$496	\$170	\$666
181			Screws	3482	0%	3482	EA	\$ 0.02	\$ 0.0	\$70	\$35	\$104
182			(2'x2') ACT Ceiling	14436	10%	15879	SF	\$ 5.63	\$ 4.6	\$89,401	\$72,410	\$161,811
183			(3/8") Thk Metal Soffit Panels W/ Wood Plank Like Vee Grooves - Kyndal Finishes Galvalum; Premium Printed Wood grain Pattern Note: Verify Whether Required Or Not And Modify Accordingly	2646	10%	2911	SF	\$ -	\$ -	\$0	\$0	\$0
			Tower Ceiling As:									
184			1/4" MDF Core Veneer Ceiling	580	10%	638	SF	\$ 6.84	\$ 4.6	\$4,364	\$2,909	\$7,273
185			5/8" Gypsum Board W/ Suspension Wire (4'x8' Sheets)	18	0%	18	EA	\$ 17.48	\$ 24.5	\$317	\$444	\$760
186			Tapping	290	10%	319	LF	\$ 0.16	\$ 0.1	\$51	\$29	\$80
187			Mudding	30	10%	33	LBS	\$ 3.50	\$ 1.2	\$116	\$40	\$156
188			Screws	816	0%	816	EA	\$ 0.02	\$ 0.0	\$16	\$8	\$24
189			1-1/2" Cold Rolled Channels @ 36" O.C (10' L)	19	0%	19	EA	\$ 14.24	\$ 13.2	\$275	\$255	\$531
190			1-1/2" Metal Furring Channels @ 18" O.C (10' L)	39	0%	39	EA	\$ 14.24	\$ 13.2	\$551	\$511	\$1,061
191			5/8" Gypsum Board Soffit	12	0%	12	EA	\$ 17.48	\$ 24.47	\$210	\$294	\$503
192			3-5/8" Metal Stud (4' H)	144	0%	144	EA	\$ 8.94	\$ 11.51	\$1,291	\$1,662	\$2,952
			Subtotal							\$281,458.59	\$242,467.65	\$523,926.24
			TOTAL AMOUNT							\$281,458.59	\$242,467.65	\$523,926.24
			Contingencies (5%)							\$14,073	\$12,123	\$26,196
			Overhead and Profit (10%)							\$28,146	\$24,247	\$52,393
			TOTAL BASE BID							\$323,677	\$278,838	\$602,515